This drawing is the property of L&T Construction, BAF-EDRC and must not be passed on to any person or body not authorised by us to receive it nor be copied or otherwise made use either in full or in part by such person or body without our prior permission in writing.

NOTE:
- ALL WALLS MAIN COLOR SHALL BE BERGER FROZEN ICE (4P1849)
- HIGHLIGHTER SHADE SILK RIBBON (T2466)

NORTH POINT

1 / 0028 THIRD FLOOR - PART-B
1 : 100

GENERAL NOTES :

01. ALL DIMENSIONS ARE IN MILLIMETERS & LEVELS IN METERS.
02. +/-0.000FFL REFERS TO 21.400 LEVEL AT SITE.
03. THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH THE ALL FLOOR PLANS, ELEVATIONS & SECTIONS O19035-A-HP-02-WD-0020 TO 0042.
04. JOINERY / STRUCTURAL GLAZING SHOWN IN PLAN ARE INDICATIVE. REFER HARDWARE SCHEDULE TEMPLATE FOR DETAILS.
05. FOR JOINERY, STAIRCASE, RAMP DETAILS, LIFTS, TOILETS, WALL SECTIONS, FLOORING PATTERN DETAILS, FURNITURE LAYOUTS & FALSE CEILING DETAILS REFER SEPARATE DRAWINGS.
06. FOR STRUCTURAL, PUBLIC HEALTH ENGINEERING, HVAC, ELECTRICAL, AND FIRE FIGHTING DETAILS REFER APPROPRIATE SEPARATE DRAWINGS.
07. AHU PEDESTAL DETAIL REFER STRUCTURAL DRAWING.
08. ALL EXTERNAL WALLS SHOULD BE BUILT UPTO SOFFIT OF BEAM OR CEILING.
09. LIFT WALL OPENING SIZES AND POSITIONING AS PER LIFT MANUFACTURER'S SPECIFICATION AND TO BE FOLLOWED AS PER THE APPROVED VENDOR DWG.
10. FOR TOILET DETAILS REFER STANDARD DRAWING.
11. FOR KITCHEN DETAILS REFER SEPARATE DRAWINGS.
12. ALL ROOF SLAB CUTOUTS INDICATED IN THIS DRAWING ARE TENTATIVE. REFER STRUCTURAL DRAWINGS FOR EXACT LOCATION.
13. ALL DIMENSIONS SHALL BE VERIFIED ON SITE PRIOR TO START OF WORK AND ANY DISCREPANCY SHALL BE BROUGHT TO THE NOTICE OF THE ARCHITECT AT EGRC.
14. ANY DISCREPANCY NOTICED SHALL BE BROUGHT TO THE ATTENTION OF THE CONSULTANTS WITHIN 7 WORKING DAYS OF RECEIVING THE DRAWING, PRIOR TO PROCUREMENT / EXECUTION OF WORK.
15. THE FURNITURE SHOWN IN THE DRAWING ARE INDICATIVE AND IS NOT IN L & T SCOPE OF WORK.
16. 100MM THK. WALL SHOULDER HAS TO BE MAINTAINED FOR ALL DOORS AND 200MM THK WALL SHOULDER AT COLUMN LOCATION OR UNLESS SPECIFIED.

WALL HATCH LEGEND:
- 250 / 150MM THK BLOCK WALL
- PROP WALL / COLUMN
- EXISTING COLUMN

CUTOUT LEGEND:
- FLOOR CUTOUT
- ROOF CUTOUT

SUNKEN LEGEND:
- 100MM FLOOR SLAB TO BE SUNKEN FROM TOC
- 300MM FLOOR SLAB TO BE SUNKEN FROM TOC

SHAFT SCHEDULE - THIRD FLOOR-PART-B

TAG	DESCRIPTION	LENGTH	WIDTH
03-SH-105	PHE SHAFT	1700	1150
03-SH-106	PHE SHAFT	600	600
03-SH-107	PHE SHAFT	1250	300
03-SH-108	PHE SHAFT	1200	300
03-SH-109	PHE SHAFT	300	1050
03-SH-110	PHE SHAFT	1150	1050
03-SH-111a	PHE SHAFT	1080	1080
03-SH-112	PHE SHAFT	2000	900
03-SH-113	PHE SHAFT	1200	600
03-SH-114	PHE SHAFT	1200	600
03-SH-115	PHE SHAFT	850	1500
03-SH-116	PHE SHAFT	1200	600
03-SH-117	PHE SHAFT	850	300
03-SH-211	HVAC SHAFT	1500	900
03-SH-212	HVAC SHAFT	1500	1400
03-SH-213b	HVAC SHAFT	1400	1400
03-SH-214	HVAC SHAFT	1500	1400
03-SH-215	HVAC SHAFT	1150	2000
03-SH-216	HVAC SHAFT	1150	1300
03-SH-217	HVAC SHAFT	900	1200
03-SH-218	HVAC SHAFT	475	2750
03-SH-219	HVAC SHAFT	1000	900
03-SH-220	HVAC SHAFT	2500	900
03-SH-221	HVAC SHAFT	1250	3500
03-SH-222	HVAC SHAFT	750	1000
03-SH-223	HVAC SHAFT	750	1750
03-SH-224	HVAC SHAFT	2400	600
03-SH-204	HVAC SHAFT	1500	550
03-SH-301	ELECTRICAL SHAFT	4000	600
03-SH-401	ELV SHAFT	300	650
03-SH-502	FPS SHAFT	300	300
03-SH-504	FPS SHAFT	375	300
03-SH-505	FPS SHAFT	300	300
03-SH-506	FPS SHAFT	300	300
03-SH-600	MGPS SHAFT	1150	950

DOOR SCHEDULE - THIRD FLOOR PART-B

TAG	WIDTH	HEIGHT	COUNT
AD14d	2400	2100	1
AD16p	1500	2100	9
FD01	2000	2100	1
FD01a	2100	2100	2
FD06	1200	2400	1
FD07	1200	2100	4
LD04	1200	2100	1
SD10c	750	2000	3
SD11a	600	1500	8
WD09	1000	2100	1
WD12L	900	2100	9
WD17	850	2100	9
WD17L	850	2100	2
WD19	1050	2100	12
WD19L	1050	2100	2
WD19x	1050	2100	36

WINDOW / VENTILATOR SCHEDULE - THIRD FLOOR-PART-B

TAG	WIDTH	HEIGHT	COUNT
AV03	1500	600	3
AV04	1800	600	2
AW01	1800	1550	12
AW01L	1800	1550	1
AW02	1500	1550	3
AW03	750	1550	1
AW08	1050	2000	3
AW22	1050	1550	6

FLOOR LEVEL 00.0-0.000 ROOM SERIAL NO. ROOM TYPE

ROOM TAG KEYNOTE:
- S - SERVICES
- T - TOILET
- L - LIFT LOBBY
- ST - STAIRCASE
- R - ROOMS

FLOOR LEVEL 00.0-0.000 SHAFT TYPE / SERIAL NO. SHAFT

SHAFT NO SHAFT TYPE

1XX	PHE
2XX	HVAC
3XX	ELECTRICAL
4XX	ELV
5XX	FEA
6XX	MGPS

LEGEND :

FRL	- FINISHED ROAD LEVEL
FFL	- FINISHED FLOOR LEVEL
FEA	- FIRE EQUIPMENT AREA
TOC	- TOP OF CONCRETE
LVL	- LEVEL
TOI	- TOILET
ELV	- EXTRA LOW VOLTAGE
PHE	- PUBLIC HEALTH ENGINEERING
HVAC	- HEATING VENTILATION AIR CONDITIONING
AHU	- AIR HANDLING UNIT
AL	- ALUMINUM LOUVER
AW	- ALUMINUM WINDOW
AD	- ALUMINUM DOOR
WD	- WOODEN DOOR
FD	- FIRE DOOR
SD	- STEEL DOOR
DA TOI	- DISABLE TOILET
PUB TOI (F)	- PUBLIC TOILET FEMALE
PUB TOI (M)	- PUBLIC TOILET MALE
F.TOI. / CH ROOM	- FEMALE TOILET / CHANGE ROOM
M.TOI. / CH ROOM	- MALE TOILET / CHANGE ROOM
	- 10MM DROP FROM FINISH FLOOR LEVEL

KEY NOTES :

1. 2100MM HIGH WALL OPENING FROM FINISHED FLOOR LEVEL. (WIDTH REFER TO PLAN)
2. CANOPY ABOVE
3. PARK WATER DOWN TAKE PIPE
4. M.S HANDRAIL TO DETAIL
5. REFER STANDARD DRAWING FOR TOILET DETAILS
6. 150MM THK. 100MM HIGH RC KERB WALL FROM FFL (REFER STRUCTURAL DRAWING)
7. FEA SHAFT DOOR 1830MM SILL FROM FINISH FLOOR LEVEL
8. STONE CLADDING TO DETAIL
9. ELV SHAFT DOOR 300MM SILL FROM FINISH FLOOR LEVEL
10. EXPANSION JOINT REFER STRUCTURAL DRAWING
11. COUNTER TO DETAIL
12. DB LOCATION
13. RECEPTION NURSES TABLE
14. RC PARAPET WALL REFER STRUCTURAL DRAWING
15. RC BEAM BEEN IN PLAN
16. 500MM WIDE RC SUNSHADE ABOVE
17. 250MM THK. 1050MM HIGH BLOCK WORK PARAPET WALL OVER 150MM HIGH M.S RAIL
18. RC SLAB TO BE EXTAND ABOVE
19. RC SLAB PROJECTION ABOVE AT LINTEL LEVEL
20. SLOPE TO BE PROVIDE
21. ACP LOUVER WITH SUPPORTING FRAME PROJECTION
22. STONE CLADDING FINISH ABOVE
23. SS HANDRAIL WITH GLASS BALUSTER TO DETAIL
24. 250MM THK. BLOCK WALL UPTO 900MM HIGH WITH FIXED GLAZING 1200MM HIGH
25. EXHAUST LOUVER FOR REFER HVAC DRAWINGS
26. 1800X1200 WALL OPENING FROM SILL LEVEL

STRUCTURAL GLAZING - THIRD FLOOR-PART-B

TAG	WIDTH	HEIGHT	COUNT
FG01	7400	1200	1
SG08	10265	2350	1

KEY PLAN
SCALE- NTS

WALL LEGEND :

1. 250MM THK. BLOCK WALLS UP TO SOFFIT OF THE SLAB/BEAM.
2. 150MM THK. BLOCK WALLS UP TO SOFFIT OF THE SLAB/BEAM.
3. 75MM THK. DRY TO DRY WALL PARTITION FROM TOC to 100mm high TOP OF THE FALSE CEILING ★
4. 75MM THK. DRY TO WET WALL PARTITION From TOC to 100mm high TOP OF THE FALSE CEILING ★
5. 75MM THK. WET TO WET WALL PARTITION From TOC to 100mm high TOP OF THE FALSE CEILING ★
6. 100MM THK. DRY TO DRY WALL PARTITION (SHAFT) UP TO SOFFIT OF THE SLAB/BEAM. ★
7. 100MM THK. DRY TO DRY WALL PARTITION (FIRE RATED) UP TO SOFFIT OF THE SLAB/BEAM. ★
8. 200MM DRY TO WET WALL PARTITION (FOR TOILET) UP TO SOFFIT OF THE SLAB/BEAM. ★
9. 200MM DRY TO DRY WALL PARTITION (FOR DB) UP TO SOFFIT OF THE SLAB/BEAM. ★
10. 200MM WET TO WET WALL PARTITION (FOR TOILET) UP TO SOFFIT OF THE SLAB/BEAM. ★
11. 200MM DRY TO DRY WALL PARTITION (FOR FIRE RATED) UP TO SOFFIT OF THE SLAB/BEAM. ★

NOTE :
*ALL PARTITION SIZES SHALL BE AS PER FINALIZED VENDER DETAILS.
- FOR DETAIL ELEVATED ROAD REFER SEPARATE ARCHITECTURE AND STRUCTURAL DRAWINGS.

CLIENT SIGNATURE :

REV.NO.	DESCRIPTION	DESIGNED	DRAWN	CHECKED	APPROVED
0	RELEASED AS GOOD FOR CONSTRUCTION	ARKH 17.01.2020	JR 17.01.2020	TI 21.01.2020	JA 21.01.2020

REVISIONS

CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE	CHECKED BY	SIGN	DATE
ARCHITECTURE			HVAC			GIS		
CIVIL & STRUCTURAL			FPS			GEOTECH		
ELECTRICAL			PIPING			VHT		
ELV SYSTEM			PHE					

CLIENT : ASSAM CANCER CARE FOUNDATION

L&T Construction — Buildings & Factories

PROJECT : Proposed Cancer Centre At 18 Locations In Assam For Assam Cancer Care Foundation & M/s. Tata Trusts
STATE CANCER INSTITUTE , GUWAHATI - PHASE-2 (A Government of Assam and Tata Trusts Initiative)

CONSULTANT: Engineering Design and Research Center (EDRC), L&T Construction - Buildings & Factories.
CONCEPT ARCHITECT: Engineering Design and Research Center (EDRC), L&T Construction - Buildings & Factories.

SUPPLIER / CONTRACTOR : Larsen & Toubro Limited, Construction, Buildings & Factories

JOB No : O19035

	NAME	SIGN	DATE
DSGN	ARKH		17.01.2020
DRWN	TJR		17.01.2020
CHKD	TI		21.01.2020
APPD	JA		21.01.2020

TITLE: HOSPITAL BLOCK
THIRD FLOOR PLAN (PART-B)

SECTION ELEVATION MARKING | DRAWING NUMBER | SCALE: As indicated

DRAWING No. O19035 - A - HP - 02 - WD - 0028

PROJECTION | SIZE: A0 | REV: 0 | SHEET | TOT.SHEE

RELEASED FOR ☐ PRELIMINARY ☐ TENDER ☐ INFORMATION ☐ APPROVAL ☑ CONSTRUCTION