

REQUEST FOR PROPOSAL (RFP)

SELECTION OF CONTRACTOR FOR INTERIOR FIT-OUT WORKS AT DIPHU CANCER CENTRE

Tender Ref No.: ACCF/Interior/2024-25/78

CORRIGENDUM-3:

Date: 28-06-2024


Pre-Bid Query Resolution




Sl. No.	Item Code.	Description of Work	Queries	Clarification/Amendment
2.00	2.01	Laminate panelling (direct on wall)		
		Fabricating and fixing of 12mm BWR ply onto the existing wall surface by means of approved wooden screws/nails and to be finished with approved 1mm laminate. To have necessary grooves as per details. To be in proper line and level as per architects instructions.	basic rate for laminate	Laminate Finish - GREENLAM LAMINATES - 776 Java Teak Paint shade: RAL 9016 Traffic White; Please explore rate from market/dealer.
		Fabricating and fixing of 12mm bwr ply boxing onto aluminium framework using 2.5mm thk 50x75 aluminium box section on the existing wall surface by means of approved screws/nails and to be finished with approved stone veneer. To have necessary grooves as per details and cost to include CNC cut "moss inlay" and cove lights as per detail drawings. To be in proper line and level as per architects instructions, all complete.	basic rate for stone veneer	Selection: Series - Stontecch, Shade - Silver Grey Quartzite Base Rate : Rs. 100 /Sq.ft (material)
5.00	5.02	Metal Ceiling (Reception, Cafeteria) Supply and fixing of Luxalon Closed Ceiling System as manufactured by Hunter Douglas Architectural Products or Equivalent. The longitudinal panels - 150mm wide and finish as per architect's choice are clipped on to Rows of 0.6 Fe/0.95 Alu roll	Please share false ceiling height and suspension height from slab	Bottom of false ceiling level is +2700 and +2800.


Sl. No.	Item Code.	Description of Work	Queries	Clarification/Amendment
		formed carrier swith max length of 5000mm . The panels abut each other with a narrow V-groove. Panels can be combined as required in the ceiling. Panels to be manufactured from pre-painted, stove enamelled, alloy HD5050 or equal (according to EN 1396 and ECCA). All panels to be securely clipped to carriers in accordance with manufacturers recommendations, Panels to be joined in length by using the relevant Luxalon splice. Maximum panel length to be 6000 mm. System to include Wall L-panel as per architect's specification option. The price should include the cost of making any cuts and openings for lights and other fittings, all inclusive.		Suspension from slab is 1400mm and 1500mm.
5.00	5.03	Stretch Ceiling (For Radio diagnostic rooms including MRI)		
		Supply and Fixing :(Brand Euroceil) ceiling with Stretch ceiling on MS structure fitted to ply boxing with Anchor fastner. Stretch material Finish : Translucent PVC Membrane Color : Printed (EC1-TR-011) GE LED with PCU Charges for Lighting Solutions CV Dimmer Repeater Circuit Design For Dimmer & Repeater with Accessories . Size as per detailed dwgs.	Please share false ceiling height and suspension height from slab	Bottom of false ceiling level is +3000 and Bottom of stretch ceiling is +3100 for Linac, +3050 for Gamma and PET Scan, +2700 for MRI and CT Scan.
6.00	BUILT-IN FURNITURE WORKS			
	6.01	Reception / Help Desk Table (Type 1)		
		<p>Providing and fixing of base table shape made of 18mm BWR ply with flap open Top and Front door wherever necessary all as per detail. Table top and supports to be made of 18mm double layer BWR ply with storage units as per design - 2 nos pull out drawers and one openable shutter (all lockable). Storage to have necessary shelves formed of 18mm BWR ply finished with 1mm antibacterial laminate. Shutters to be postformed. Shutters to be provided with necessary hardwares like spring loaded hinges, tower bolts, SS handles, magnetic catchers and locks etc., of approved make and quality. Cost to include keybord tray, cpu tray, wire management wherever applicable and should include fixing of LED strip lighting as per design all complete. Cost also to include Vertical Tabletop Panel along edge of table wherever applicable as per detail drawing. Cost also to include antitermite treatment / borer treatment for plywood.</p> <p>>> All the exposed surfaces (Outer and Inner vertical surfaces) to be finished with 1mm thk antibacterial laminate - 55% of Exterior Finishes in 1mm Laminate.</p> <p>>> Rate inclusive of Solid Acrylic Surface material at locations (Table Top and Front Fascia) all as specified as per drawing - horizontal and vertical surfaces to have 12mm Solid Acrylic Surface (including Curved edges, curved surfaces etc) and</p>	basic rate for solid surface	<p>Please explore rates for Acrylic Solid surface - Corian - Camio White / LG - TAMBORA VE 01 / LG -OPAL32 or similar approved Shade in line with the respective Interior Concept Presentation.</p> <p>Laminate : GREEN LAM LAMINATES - 776 Java Teak</p>

Sl. No.	Item Code.	Description of Work	Queries	Clarification/Amendment
		<p>inclusive of required fixing materials & clear adhesives, and to include magaram joint, buffing, pasting, making of cut outs etc as per design, all complete. Note - Curved surfaces cost to include thermoforming, etc all complete. Cost to be inclusive of 12mm ply backing with framing for solid acrylic surface material. - <u>45% of Exterior Finishes in Solid Acrylic Surface material.</u> >> Inside surfaces to be finished with 1mm thk antibacterial laminate and with 2mm PVC Edge Bands and SS corners wherever required as per drawing. - <u>50% of running length to have storage (which includes 2 drawers and 1 openable shutter) with inside finish with 1mm antibacterial laminate.</u></p> <p>>>Table Dimension: Height is 750mm(Table Top- Part) & 1050mm - Solid Acrylic Surface (Ledge Top - Part) Depth is 750mm all as per drawing</p>		
	6.02	Reception Table / Help Desk (Type 2)		
		<p>Providing and fixing of base table shape made of 18mm BWR ply with flap open Top and Front door wherever necessary all as per detail. Table top and supports to be made of 18mm double layer BWR ply with storage units as per design - 2 nos pull out drawers and one openable shutter (all lockable). Storage to have necessary shelves formed of 18mm BWR ply finished with 1mm antibacterial laminate. Shutters to be postformed. Shutters to be provided with necessary hardwares like spring loaded hinges, tower bolts, SS handles, magnetic catchers and locks etc., of approved make and quality. Cost to include keyboard tray, cpu tray, wire management wherever applicable and should include fixing of LED strip lighting as per design all complete. Cost also to include Vertical Tabletop Panel along edge of table wherever applicable as per detail drawing. Cost also to include antitermite treatment / borer treatment for plywood. >> All the exposed surfaces (Outer and Inner vertical surfaces & Table Top) to be finished with 1mm thk antibacterial laminate - <u>70% of Exterior Finishes in 1mm Laminate.</u></p> <p>>> Rate inclusive of Solid Acrylic Surface material at locations as specified as per drawing - horizontal and vertical surfaces to have 12mm Solid Acrylic Surface (including Curved edges, curved surfaces etc) and inclusive of required fixing materials & clear adhesives, and to include magaram joint, buffing, pasting, making of cut outs etc as per design, all complete. Note - Curved surfaces cost to include thermoforming, etc all complete. Cost to be inclusive of 12mm ply backing with framing for solid acrylic surface material. - <u>30% of Exterior Finishes in Solid Acrylic</u></p>	basic rate for solid surface	<p>Please explore rates for Acrylic Solid surface - Corian - Camio White / LG - TAMBORA VE 01 / LG -OPAL32 or similar approved Shade in line with the respective Interior Concept Presentation.</p> <p>Laminate : GREEN LAM LAMINATES - 776 Java Teak</p>

Sl. No.	Item Code.	Description of Work	Queries	Clarification/Amendment
		<p><u>Surface material.</u></p> <p>>> Inside surfaces to be finished with 1mm thk antibacterial laminate and with 2mm PVC Edge Bands and SS corners wherever required as per drawing. - 50% of running length to have storage (which includes 2 drawers and 1 openable shutter) with inside finish with 1mm antibacterial laminate.</p> <p>>>Table Dimension:</p> <p>Height is 750mm(Table Top- Part) & 1050mm - Solid Acrylic Surface (Ledge Top - Part)</p> <p>Depth is 750mm all as per drawing</p>		
	6.03	Doctor's Consultation Worktable	can we provide from our factory	Yes. But, ACCF reserves the right to visit your factory to inspect before giving final approval.
		Size- Main Table : 1500 x 750, Return Table :900 x 450		
		Table Top -Prelam PVC lipping		
		Understructure : Aluminium		
		RaceWay - below Table		
		Accessories : Mobile Pedestal - 1 No (2 draws ans 1 openable shutter) & Side Storages with shelves with 2 openable shutters, all complete.		
7.00	7.04	<p>Roller Blinds:</p> <p>>Providing & fixing Roller blinds confirming to specifications, including spring mechanism</p> <p>>The Drive units -Shall be of moulded plastic with rectangular support pin and inserted into the tube end .It shall be driven by a ball chain pulley with ball chain and can be positioned at right hand or left hand side of the shade.The shade when lowering or raising ,shall be automatically locked in position upon release of the ball chain by means of built in friction lock.</p> <p>>End Plug-Shall be moulded of plastic with alocation pin .The plug shall be inserted into tube end.(Opposite to drive unit)</p> <p>>Support Brackets-Shall be of zinc plated steel & provided with moulded plastic covers and used in right hand or left hand positions differentiated by the acceptance of the rectangular drive unit support or the round idler plug pin.</p> <p>>Bottom Rails-Shall be stiffening element inserted into abottom rod pocket.The</p>	Please share basic rate	<p>Please explore rates for Roller Blinds:</p> <p>Phifer- P75 PEARL / V16 GREY / or Equivalent with approved shade</p> <p>Vendor details as follows:</p> <p>M/s Phifer - Mr.Yogesh, 8884311112</p> <p>M/s Vista - Mr.V.FAIAZ AHAMED, 9840466044</p> <p>M/s Hunter Douglas - Mr.Subramani, 8754448500</p>

Sl. No.	Item Code.	Description of Work	Queries	Clarification/Amendment
		<p>material may be timber ,PVC covered steel tube or VB bottom rail.</p> <p>>Ball Chain -Shall be 2mm diameter cord with 4.5mm diameter acetal balls moulded co-axially to it on 6mm pitch to form a endless ball chain .It is used for raising or lowering action of the shades.</p> <p>>Fabric</p> <p>1) Basic material -100% antimicrobial - polyester - translucent</p> <p>2) fabric weight -170g/sqm</p> <p>3) Thickness -4mm</p> <p>5) Finishing -Double side vinyl acetate, pigment coated</p> <p>>Light Fitness -Confirming to DIN54004/DIN EN ISO 105-B02>/5-6</p> <p>>Shrinkage % ge-Confirming DIN 53892 B2 <0.5%</p> <p>> 1% Perforation factor - (Code- Solaris Fabric Panel-1%-Sol Series-001)</p>		
	7.12	<p>Planter Box:(with artificial potted plants)</p> <p>450x600x450mm, made of BWR ply with 1mm laminate finish outside and 0.8mm inside, design as per architects detail drawings, to place potted plants of height of about - 1050mm to 750mm, Pebbles- cost inclusive of pebbles of approved colour - Grey, white, black. Sizes varying from 25mm to 50mm. Basic cost 25 kg bags - 2500.</p>	Please share vendor details	It can be factory fabricated and assembled at site.
	7.13	Light Fixtures:		
		A) Reception Table Backdrop Track Lighting Set with 9 Spot Lights	Please share reference images along with how many wats is required.	

Sl. No.	Item Code.	Description of Work	Queries	Clarification/Amendment
		B) OPD Waiting Feature Wall Lighting Set (10 Spots)	Please share reference images along with how many wats is required.	 
		C) IPD Waiting Feature Wall Lighting Set (5 Pendant Light)	Please share reference images along with how many wats is required.	Similar to the above.
		D) Cafeteria Pendant Lights	Please share reference images along with how many wats is required.	Not required.
		E) LED Strip Light	Please share reference images along with how many wats is required.	<p>Its normal strip light only. Wattage can vary from 2 to 4 watts.</p> 

Sl. No.	Item Code.	Description of Work	Queries	Clarification/Amendment
				
	7.14	SS Signage:		
		A) Reception SS Logo + Lettering fixed on wall / paneling	Please share outer dimensions	600mmX700mm to 900mmX1100mm. Please refer images provided.
		B) SS Signage (Emergency)	Please share outer dimensions	600mmX700mm to 900mmX1100mm. Please refer images provided.
		C) Lift Lobby Floor Indication SS Signage	Please share outer dimensions	600mmX700mm to 900mmX1100mm. Please refer images provided.
	7.15	Artefacts / Artist's Painting		
		Artwork - 1 - 1000x1200mm	Please share basic rate or vendor details	Rs.8,000(Set-up cost per artwork)
		Artwork - 2 (Bamboo) 1000x600mm	Please share basic rate or vendor details	Rs.11000 full finish
		Artwork - 2 (Artist's Painting- Printed on Canvas) (LINAC / Consultation Room) - 600X600MM	Please share basic rate or vendor details	Rs.3500 full furnish
	7.16	Feature Wall - 01 (OPD Lounge)		
		Fabricating and fixing 10900 width x 2700mm HT Feature wall elements all complete - Stone Veneer with framework and ply backing, CNC Cut Moss strip on wall, vertical laminated HDF boards, vertical duco painted ply boards all as per architect's detail drawing, including Powder coated MS letterings fixed on wall.	Basic rate for stone veneer, moss	Rate to be arrived by Bidder as per the detailed drawing prepared by them based on Specifications provided. Vendor details: M/s Amber Furniture Mr.Balaji - 009444379963 Balajnb@yahoo.com
2.00	Fixed Seats			

Sl. No.	Item Code.	Description of Work	Queries	Clarification/Amendment
	2.01	10S Island Seat (Reception) -Fabricating and Supply of Floor Mounted 10S Island seat with BWR Ply and M/S framework as required with BWR Ply cover / Flexibly cover with PU Leather finish as per approved colour, all complete as per architect's drawing.	Please share size and drawings	3150mmX1300mm. Please refer AutoCAD Drawing. However, it is a preliminary furniture layout. Shop drawing shall have to be done by the shortlisted interior vendor after this tender is closed.
	2.02	Bamboo Seater-Type 1 (Reception) -Fabricating and Supply of Floor Mounted Bamboo Seat with Necessary Ply and MS Framework all complete as per detail drawing.	Please share size and drawings	1300mmX500mm. Please refer AutoCAD Drawing. However, it is a preliminary furniture layout. Shop drawing shall have to be done by the shortlisted interior vendor after this tender is closed.
	2.03	Bamboo Seater-Type 2 (Reception / OPD Lounge) -Fabricating and Supply of Floor Mounted Bamboo Seat with Necessary Ply and MS Framework all complete as per detail drawing.	Please share size and drawings	1300mmX500mm. Please refer AutoCAD Drawing. However, it is a preliminary furniture layout. Shop drawing shall have to be done by the shortlisted interior vendor after this tender is closed.
3.00	OTHERS (TABLES & STORAGES)			
3.01	T1	Office Table		
		The worktop is made of 25mm thick prelaminated particle board with 2mm thick PVC Lipping on the edges. The worktop is supported on loop shape Metal Legs 50mm x50mm powder coated under structure with laminate panel. Side Storage body is a combination of 3 drawer pedestal unit and a hinged door unit and is s made of 18mm thick pre laminated particle Board conforming to IS:12823 and is hinged door unit . The back of the unit is made from 18mm prelaminated board. All the exposed edges are with 2mm PVC edge approved make banding and sealed edges are with 0.8mm thick PVC approved make edge banding. The top side and hinged shutters are sealed	Please share size and drawings, can we provide from our factory.	Please refer AutoCAD Drawing. It can be factory fabricated, but ACCF reserves the right to visit your factory to inspect before giving final approval.

Sl. No.	Item Code.	Description of Work	Queries	Clarification/Amendment
		with 2mm thick PVC edge banding. Back the unit are assembled by knock down fitting such as Minifix and Dowels. All the hardware and Hinges are from Hettich/Ebco. Warranty 5 years.		
3.02	T2	Workstation I Shape		
		Curvilinear Workstation 1500 L x 600W x 1200 L x 600W x 1200mm Ht with pedestal unit Frame is 50 mm thick and made of Aluminium Extrusions of 1.2 mm to 1.5mm thickness. The System is complete hollow system with space for wire reticulation. All the frames will be duly power coated. All the frames are fastened together by means of M6 NUTS & BOLTS. All the frames are fitted with M10 levelling bolts, board. Race way -The race way cover are sliding type and are integrally fitting inside frame and are made out of 0.8mm-1mm thick CRCA steel & powder coated. The electrical raceway can be provided below worktop or above worktop. The partition has two integrated raceways provided one at skirting level and another at the work surface level thus ensuring separation of power and networking cables. The free space available within raceway accommodates power, data and communication cables. The cable can be taken into the frame from the floor from the bottom. Tiles: Fabric Tile; constructed out of 5mm thick Medium Density Fiber Board (MDF) and covered with Fabric of choice. Laminate Tile; constructed out of 0.8 mm CRCA sheet and laminated Medium Density Fibre Board (MDF) Bottom Row of steel Tile; Made out of 5mm-8mm thick pre-laminated Medium Density Fiber Board (MDF) Bottom Row of steel Tile ; Constructed finished in epoxy powder coating. Can be given with plain /perforations/embossed finishes Magnetic tile; Constructed out of 0.8mm Galvanized sheet and covered with fabric of choice. Whiteboard marker tile: Made out of 4mm MDF with 1mm glossy highly wear resistant face laminate-Total thickness is 5mm. Table tops are of 25mm thick pre-laminated particle boards conforming to IS:12823 Interior Grade. All Worktops to have Metal Insets for fixing screws. Specially designed powder coated M.S brackets having 2mm thickness fixed to the partition frame support the tabletops.	Please share size and drawings.	1500 L x 600W x 1200 L x 600W x 1200mm Ht. is mentioned in the BOQ. Please refer AutoCAD Drawing. However, it is a preliminary furniture layout. Shop drawing shall have to be done by the shortlisted interior vendor after this tender is closed.


Sl. No.	Item Code.	Description of Work	Queries	Clarification/Amendment
		Sealed edge in tabletops are with 2mm thick PVC edge banding on working side and 0.8mm thick edge banding on non-working side. Legs are made of powder coated steel 50mmx50mm section. Cross Member are in CRCA steel and the Beam is made of MS of 1.5mm thickness in powder coated finish of 50 microns thicknees -Each workstation has 3D raver pedestal unit of size 400mm L x 450mm D x 680 mm made up of 18mm thk prelam particle board conforming to IS:12823 Interior Grade with 3 Drawer (2 Drawer + 1 Filing) with roller side mechanism for 2 Drawers and Ball bearing slide for 1 Filing unit. Warranty 10 years.		
3.03	T9	Workstation 2		
		<p>Curvilinear Workstation 2000 L x 750 W x 1200mm Ht with pedestal unit Frame is 50 mm thick and made of Aluminium Extrusions of 1.2 mm to 1.5mm thickness. The System is complete hollow system with space for wire reticulation. All the frames will be duly power coated. All the frames are fastened together by means of M6 NUTS & BOLTS. All the frames are fitted with M10 levelling bolts, board. Race way -The race way cover are sliding type and are integrally fitting inside frame and are made out of 0.8mm-1mm thick</p> <p style="text-align: center;">Workstation 2</p> <p>CRCA steel & powder coated. The electrical raceway can be provided below worktop or above worktop. The partition has two integrated raceways provided one at skirting level and another at the work surface level thus ensuring separation of power and networking cables. The free space available within raceway accommodates power, data, and communication cables. The cable can be taken into the frame from the floor from the bottom. Tiles: Fabric Tile; constructed out of 5mm thick Medium Density Fiber Board(MDF) and covered with Fabric of choice. Laminate Tile; constructed out of 0.8 mm CRCA sheet and laminated Medium Density Fibre Board(MDF) Bottom Row of steel Tile; Made out of 5mm-8mm thick thick pre-laminated Medium Density Fiber Board (MDF) Bottom Row of steel Tile ; Constructed finished in epoxy powder coating. Can be given with plain</p>	Please share size and drawings.	<p>2000 L x 750 W x 1200mm Ht. is mentioned in the BOQ.</p> <p>Please refer AutoCAD Drawing. However, it is a preliminary furniture layout. Shop drawing shall have to be done by the shortlisted interior vendor after this tender is closed.</p>

Sl. No.	Item Code.	Description of Work	Queries	Clarification/Amendment
		/perforations/embossed finishes Magnetic tile; Constructed out of 0.8mm Galvanized sheet and covered with fabric of choice. Whiteboard marker tile; Made out of 4mm MDF with 1mm glossy highly wear resistant face laminate- Total thickness is 5mm. Table tops are of 25mm thk pre-laminated particle boards conforming to IS:12823 Interior Grade. All Worktops to have Metal Insets for fixing screws. Specially designed powder coated M.S brackets having 2mm thickness fixed to the partition frame support the tabletops. Sealed edge in table tops are with 2mm thick PVC edge banding on working side and 0.8mm thick edge banding on non working side. Legs are made of powder coated steel 50mmx50mm section. Cross Member are in CRCA steel and the Beam is made of MS of 1.5mm thicknees in powder coated finish of 50 microns thicknees -Each workstation has 3D rawer pedestal unit of size 400mm L x 450mm D x 680 mm made up of 18mm thk prelam particle board conforming to IS:12823 Interior Grade with 3 Drawer (2 Drawer + 1 Filing) with roller side mechanism for 2 Drawers and Ball bearing slide for 1 Filing unit. Warranty 10 years.		
3.06	S1	Lockers		
		Providing and supplying steel single Tower Locker Cabinets of approved make & model with in-built Locks having dimension of 1800mm H x460mm D x390mm W made of 0.8mm thick CRCA sheet duly powder coated to thicknees of 40-60 micron. Each vertical unit has SIX Nos Locker unit. Each unit has independent door with concealed hinges and 7 lever cam look and label holder the product has leveller for good ground support. All the components are finished 40 to 50 microns thick epoxy polyester powder coating oven baked at 180to 200 deg.C. The above furniture should be as per specification and sample approved by client.	Please mention the make	Featherlite, Godrej or equivalent.
	1	The scope of work includes preparation of detailed Interior GFC / shop drawings covering all the areas including all furniture layouts, interfacing with base architectural finishing details. These drawings shall be reviewed and approved by the Consultant for execution at site.	Scope of works includes preparation of GFC drawings. Please reconfirm	Yes. Shop drawings to be provided before execution/order.

Sl. No.	Item Code.	Description of Work	Queries	Clarification/Amendment
3.00	PANELING WORKS			
	3.02	Laminate paneling - 100mm THK(with spacers) (ICU / Chemotherapy / Single Room / General Ward)	Please given centre to centre distance between vertical & horizontal members for the aluminium framework	600mmX600mm C/C.
	3.03	Stone Veneer panelling (with spacers) (Reception / Help Desk / Radiotherapy Backdrops)	Please give centre to centre distance between vertical & horizontal members for aluminium framework. Basic rate required of the stone and alom with detail drawing of the panelling	600mmX600mm C/C. Detail shop drawings to be provided by interior contractor.
4.00	WALL FINISHING WORKS			
	4.01	ACRYLIC EMULSION PAINTING: (Stencil Type - 1 - Leaf Strip Pattern) (Emergency / Radiotherapy / ICU / Chemo / Cafeteria / Single Room)	Basic rate required of the stencil painting	This is clarified as Acrylic Emulsion Stencil Painting. Design - pattern already provided. No separate rate.
	4.02	ACRYLIC EMULSION PAINTING: (Stencil Type - 2 - Leaf Pattern) (Single Room)	Basic rate required of the stencil painting	This is clarified as Acrylic Emulsion Stencil Painting. Design - pattern already provided. No separate rate.
	4.03	ACRYLIC EMULSION PAINTING: (Stencil Type - 3) (Reception / Emergency / LINAC / Radiotherapy / Cafeteria / OPD Waiting / IPD Waiting / OPD Corridor / ICU / Chemotherapy)	Basic rate required of the stencil painting	This is clarified as Acrylic Emulsion Stencil Painting. Design - pattern already provided. No separate rate.
5.00	FALSE CEILING & ASSOCIATED WORKS			
	5.01	Designer Gypboard ceiling Drops	False ceiling layout required	Shall be provided after award of the work.

Sl. No.	Item Code.	Description of Work	Queries	Clarification/Amendment
6.00	BUILT-IN FURNITURE WORKS			
	6.01	Reception / Help Desk Table (Type 1)	Detail drawing required. Basic rate required of solid acrylic surface	Detail Shop drawing shall have to be done by the shortlisted interior vendor after this tender is closed.
	6.02	Reception Table / Help Desk (Type 2)	Detail drawing required. Basic rate required of solid acrylic surface	Detail Shop drawing shall have to be done by the shortlisted interior vendor after this tender is closed.
	6.04	Full Height Storage Unit (LINAC)	Please give complete dimensions of the storage along with detail drawing	Drawing provided
	6.05	Work counter with Overhead Storage (LINAC CONSOLE)	Detail drawing required	Drawing provided
	6.06	Consultation room - Wash Basin counter	Basic rate required of the solid acrylic surface	Please explore rates for Acrylic Solid surface - Corian - Camio White / LG - TAMBORA VE 01 / LG -OPAL32 or similar approved Shade in line with the respective Interior Concept Presentation.
	6.08	Cafeteria Cash Counter (Visitor)	Detail drawing required	Please refer AutoCAD Drawing. However, it is a preliminary furniture layout. Shop drawing shall have to be done by the shortlisted interior vendor after this tender is closed.
	6.09	Cafeteria / Pantry L Shaped Service Counter	Detail drawing required	Please refer AutoCAD Drawing. However, it is a preliminary furniture layout. Shop drawing shall have to be done by the shortlisted interior vendor after this tender is closed.

Sl. No.	Item Code.	Description of Work	Queries	Clarification/Amendment
	6.10	Storage Unit (Single Room, Twin Sharing Room)	Detail drawing required	Please refer AutoCAD Drawing. However, it is a preliminary furniture layout. Shop drawing shall have to be done by the shortlisted interior vendor after this tender is closed.
	6.11	Under Counter Storage Units (All areas)	Detail drawing required	Please refer AutoCAD Drawing. However, it is a preliminary furniture layout. Shop drawing shall have to be done by the shortlisted interior vendor after this tender is closed.
7.00	Miscellaneous Work			
	7.01	Colour Frost film	Basic rate required	Make: 3M or equivalent make. Vendor Contact details as Below: M/s SIGNTIST Graphics - Mr. Praveen, 9884948600 or any others as per Concept Presentation & Specifications NOTE : Interior Contractor must develop the Custom Design with 3M or equivalent make using the Graphics Vendor. The Film pattern should be matching in line with the Concept Presentation.
	7.02	Wall Vinyl graphics (Single Room / Consultation Room / Cafeteria)	Basic rate required	Vendor Contact details as Below: M/s Emagine India- 9916631250 or M/s Blue Pebble- 9768199800 or M/s SIGNTIST Graphics - Mr. Praveen, 9884948600 NOTE : Interior Contractor must develop

Sl. No.	Item Code.	Description of Work	Queries	Clarification/Amendment
				all the necessary required resolution using the Graphics Vendor. The Graphics line with the Concept Presentation using Presets from developed subject to Approval by Client / Architect.
	7.04	White Board (Nurse Station)	Basic rate required	Base Rate Rs.3500/-
	7.07	SS Glazed Railing (OPD & IPD Waiting feature wall)	Detail drawing required	<p>Please refer Photograph. However, it is a preliminary furniture layout. Shop drawing shall have to be done by the shortlisted interior vendor after this tender is closed.</p> 
	7.10	Mesh top Anti-Microbial Fabric Curtains	Basic rate required	Rs.500/-
	7.13	Light Fixtures:		
		A) Reception Table Backdrop Track Lighting Set with 9 Spot Lights	Make & model number required	Make can be Hevels, Colors, Philips, Wipro, etc. Models can be selected later as the item is not having much price weightage for different models.
		B) OPD Waiting Feature Wall Lighting Set (10 Spots)	Make & model number required	
		C) IPD Waiting Feature Wall Lighting Set (5 Pendant Light)	Make & model number required	
	7.14	SS Signage:		
		A) Reception SS Logo + Lettering fixed on wall / paneling	Size & detail specifications required	600mmX700mm to 900mmX1100mm. Please refer images provided.

Sl. No.	Item Code.	Description of Work	Queries	Clarification/Amendment
		B) SS Signage (Emergency)	Size & detail specifications required	600mmX700mm to 900mmX1100mm. Please refer images provided.
		C) Lift Lobby Floor Indication SS Signage	Size & detail specifications required	600mmX700mm to 900mmX1100mm. Please refer images provided.
	7.15	Artefacts / Artist's Painting		
		Artwork - 1 - 1000x1200mm	Basic rate required	Rs.8,000(Set-up cost per artwork)
		Artwork - 2 (Bamboo) 1000x600mm	Basic rate required	Rs.11000 full finish
		Artwork - 2 (Artist's Painting- Printed on Canvas) (LINAC / Consultation Room) - 600X600MM	Basic rate required	Rs.3500 full furnish
PART B				
1.00	LOOSE SEATS			
1.09	T8	Cafeteria ISOTOP Table with 1mm Laminate	Table Kindly share size and base detail	Please refer AutoCAD Drawing.
2.00	FIXED SEATS			
	2.01	10S Island Seat (Reception) -Fabricating and Supply of Floor Mounted 10S Island seat with BWR Ply and M/S framework as required with BWR Ply cover / Flexiply cover with PU Leather finish as per approved colour, all complete as per architect's drawing.	Please provide detail drawing with size	3150mmX1300mm. Please refer AutoCAD Drawing. However, it is a preliminary furniture layout. Shop drawing shall have to be done by the shortlisted interior vendor after this tender is closed.
	2.02	Bamboo Seater- Type 1 (Reception) -Fabricating and Supply of Floor Mounted Bamboo Seat with Necessary Ply and MS Framework all complete as per detail drawing.	Kindly provide basic rate	Rs.27000 full furnish
	2.03	Bamboo Seater- Type 2 (Reception / OPD Lounge) -Fabricating and Supply of Floor Mounted Bamboo Seat with Necessary Ply and MS Framework all complete as per detail drawing.	Kindly provide basic rate	Rs.27000 full furnish
	2.04	Wall mounted Table (around Column) (Visitor) -Fabricating and Supply of Wall Mounted Ply Table in 1mm Laminate Finish and	Please provide detail drawing with size	Please refer AutoCAD Drawing and drawing provided. However, it is a preliminary furniture layout. Shop

Sl. No.	Item Code.	Description of Work	Queries	Clarification/Amendment
		2mm Edge Banding with Necessary Ply and MS Framework all complete as per detail drawing.		drawing shall have to be done by the shortlisted interior vendor after this tender is closed.
	2.05	Cafeteria Wall Fixed Table (Visitor) -Fabricating and fixing of wall mounted High Table of depth 450mm all around the column / along specified length on wall etc with Ply supports in Laminate finish, including of all necessary hardware, 2mm edge banding all complete as per drawing.	Please provide detail drawing with size	Please refer AutoCAD Drawing. However, it is a preliminary furniture layout. Shop drawing shall have to be done by the shortlisted interior vendor after this tender is closed.
	2.06	Cafeteria Wall Fixed Table (Staff) -Fabricating and fixing of wall mounted High Table of depth 450mm all around the column / along specified length on wall etc with Ply supports in Laminate finish, including of all necessary hardware, 2mm edge banding all complete as per drawing.	Please provide detail drawing with size	Please refer AutoCAD Drawing. However, it is a preliminary furniture layout. Shop drawing shall have to be done by the shortlisted interior vendor after this tender is closed.
	2.07	Cafeteria Booth Seat (Staff) -Fabricating and supply of Booth seat 1000mm length - frames to be made of wooden batten and BWR ply. Seat and back rest to be made in ply, foam and leatherette(colour as per architect's selection).100mm thick foam (should be HR&FR rated) having ILD 41. , all complete as per architect's drawing .	Please provide detail drawing	Please refer AutoCAD Drawing. However, it is a preliminary furniture layout. Shop drawing shall have to be done by the shortlisted interior vendor after this tender is closed.
3.00	OTHERS (TABLES & STORAGES)			
3.01	T1	Office Tble	Please provide drawing with size	Please refer AutoCAD Drawing. However, it is a preliminary furniture layout. Shop drawing shall have to be done by the shortlisted interior vendor after this tender is closed.
3.04	T3	Conference table	Please provide drawing	Please refer AutoCAD Drawing. However, it is a preliminary furniture layout. Shop drawing shall have to be done by the shortlisted interior vendor after this tender is closed.

Sl. No.	Item Code.	Description of Work	Queries	Clarification/Amendment
3.05		Conference table	Please provide drawing with size and finishes details	Please refer AutoCAD Drawing. However, it is a preliminary furniture layout. Shop drawing shall have to be done by the shortlisted interior vendor after this tender is closed.

Other terms and conditions of tender remain the same.

-Sd-
AGM Procurement, ACCF